



Gulf Coast Water Authority

3630 Highway 1765

Texas City, Texas 77591

409.935.2438

fax 409.935.4156

ADDENDUM NO. 2

April 6, 2015

TO: Prospective Bidders

Re: **Project No. 06.20.20150318**

Fence Improvements at Thomas S. Mackey WTP

NEW BIDS DUE: April 10, 2015 AT 10:00 AM

This Addendum forms a part of the Bid Documents and will be incorporated into the Contract documents, as applicable. Insofar as the original Project Manual and Drawings are inconsistent, this Addendum governs.

Document 00210, Supplemental Instructions to Bidders, Under Item 9.0.A.1., Change the Bid Submission date to "10:00 a.m., local time on April 10, 2015".


Document 00410, Bid Form, revise bid form as follows:

- 1) Change Item description for item no. 2 to read, Fence, 7' tall fabric with 3 strands of barb wire, Including Posts, Top Rail, and corner posts.
- 2) Change Unit Quantity for item no. 4, "Swing Gate, 6' tall with 3 strands of barb wire, 8' long each" from 2 to 4.
- 3) Change Item description for item no. 5 to read, Swing Gate, 6' tall with 3 strands of barb wire, 12' long each, 6" diameter Posts, set 4' deep, minimum.
- 4) Change Unit Quantity for Item No. 8, "Remove existing fence and gates" from 440 to 940.

Clarification to the Scope of Work. Add the following requirements:

- 1) Replace Fence Fabric, 6' tall shall include straightening of vertical posts to a "Plumb Alignment." Drill hole in dirt adjacent to post, adjust post to a vertical alignment, and place concrete in hole.
- 2) Replace Fence Fabric, 6' tall will include a bottom tension wire.
- 3) Contractor shall provide sanitary facilities for workers to use for the duration of the work.
- 4) All line posts shall be 2 5/8" diameter and corner posts shall be 4" diameter.

END OF ADDENDUM NO. 2


James E. Vanderwater, P.E.
Engineer
Gulf Coast Water Authority

